



# ***F*oundation/Slab per Geotechnical Engineer Report**

Policy and Procedure-

[January] 2020

The geotechnical engineer, Neil O. Anderson and Associates, Inc. provided an addendum for uniform slab construction recommendations for subdivisions which will be enforced by the City of Lodi as follows:

1. 4 inches of clean gravel, covered with one layer of 10 mil visqueen. Gravel may be eliminated if 2 layers of 6 mil visqueen are installed with overlapping seams and draping to the bottom of the footings
2. 2 inches of sand cover over the visqueen
3. 4 inch thick slab
4. Welded wire fabric (sheets only) or #3 rebar @ 18 inches each way